DIVISION7.GR7 **Drainage Structures, Storm Sewers, Sanitary Sewers, Water Mains, and Conduits**

7-01.GR7 **Drains**

7-01.SA1.GR7 (Media Filter Drains)
(September 2, 2025)
Use in all projects with Media Filter Drains. Media Filter Drain (MFD) is paid for by the SY and informational quantities should be provided in the Contract. MFD Details in the plans should show pay limits from the edge of shoulder to the catch point. The items, Clearing and Grubbing and Seeding, Fertilizing, and Mulching should be included as a separate pay item. For additional information, refer the Highway Runoff Manual.

7-SA1.GR7 **Glass Reinforced Thermosetting Plastic (GRP) Cured-in-Place Pipe (CIPP) Lining UV Cure**
(June 1, 2026)
Use in all projects when CIPP Lining is specified by the Hydraulic Designer.

Must use with **7-SA2.GR7**.

7-SA2.GR7 **Video Pipe Inspection**
(June 1, 2026)
Use when Video Pipe inspection is specified by the Hydraulic Designer. The Hydraulic Designer will determine which pay items to include.